

Sunnyside Division Board of Control

***Sunnyside Canal Improvement Project
MP 37.10 Reservoir***

ADDENDUM NO. 4

Issued: July 12, 2010

To All Reservoir Plan Holders:

You are hereby notified of the following changes, deletions, additions, corrections and clarifications to the reservoir plans and other documents comprising the MP 37.10 Reservoir plans and specifications for the Sunnyside Division Board of Control.

CHANGES TO PART 1 – BIDDING REQUIREMENTS:

1. Section 00300 Bid Form – Page 5, Bid Item Number 14 – Description should read “Zone 3B Material for Road Subgrade and Zone 3C Material for Road Surfacing.” Bid Item remains Lump Sum.

CHANGES TO PART 4 – SPECIFICATIONS:

1. Section 01025 Measurement and Payment – Page 4, Item 10 should read “Zone 2A Material for Embankment Chimney Filter/Drain: Includes excavation and processing of material to meet requirements stated in Section 02201, Earthwork, staging the material (as necessary), moving the material, and placement and compaction of the material to the lines and grades shown on the Drawings. There will be no measurement for payment associated with this Work.”
2. Section 01025 Measurement and Payment – Page 4, Item 11 should read “Zone 2A Material for Protection Over Portion of Reservoir Bottom: Includes excavation and processing of material to meet requirements stated in Section 02201, Earthwork, staging the material (as necessary), moving the material, and placement and compaction of the material to the lines and grades shown on the Drawings. There will be no measurement for payment associated with this Work.”
3. Section 01025 Measurement and Payment – Page 5, Item 14 should read “Zone 3B Material for Road Subgrade and Zone 3C Material for Road

Surfacing: Includes excavation and processing of material at the offsite quarry to meet the requirements stated in Section 02201, Earthwork, hauling material to the reservoir site, stockpiling the material at the Project Site in the staging area (as necessary), and placement and compaction of the material to the lines and grades shown on the Drawings. There will be no measurement for payment associated with this Work.”

In order to ensure that all addenda are received by plan holders, we ask that you e-mail or fax back to us acknowledgement that you successfully received this notification. Please sign below and immediately email this page back to the Sunnyside Valley Irrigation District office at startupc@svid.org or fax to (509) 837-2088.

Company – (Please Print)

Signature

Date

Attachments: None